NorthSTAR User Manual APD detailed info Version 3: 2.14.20



NorthSTAR Agency User Manual

Application for Permit to Drill

This manual contains detailed information on how to enter information into NorthStar based off operator's documents. The permit which was utilized was approved by the NDIC Oil & Gas Division January 12, 2018. NDIC File No. 34478.


Operator Information → Required to submit the NorthSTAR application.

NDIC Oil & Gas Division Staff verification Agency will verify and correct as needed.


Step 3: Well Information

Note: You may fill in the Associated Bond (if known). The Associated Field Inspector may be found on our GIS Map Server. The Permit Fee is \$100 for an APD.

{NDIC Pierre Top pick & Min Required Surface Casing are NDIC Oil & Gas Division Staff fields}




The Multi-Well Pad Number is a NDIC Oil & Gas Division Staff field. The Magnetic Declination may be found at this web address: https://www.ngdc.noaa.gov/geomag/calculators/magcalc.shtml#declination



Step 4: Geologic Information

Note that although the applicant may request a waiver for Density/Porosity & Restivity on this form, a formal request must be made via NorthSTAR Sundry Notice. The director may consider waiving open hole logs based on viable logs within one mile of the permitted well location.





^{*&}quot;YES" is the only acceptable answer on → Cement Evaluation (required type) and Gamma to ground level (required type).

Step 4: Geologic Information Continued

The applicant must enter <u>all</u> geologic zones of significance.

^{**&}quot;YES" or "Request Waiver" are acceptable answers on Density/Porosity (Required Type) or Resistivity (required type).





*Minimum info required.

			▼ Advanced Filtering	Actions ▼	₽
Zone Name	Zone Category	Top TVD (ft) ↑	Bottom TVD (ft)	Actions	
Lodgepole Fm.	Geologic Top	10395		Actions▼	
False Bakkn	Geologic Top	11101		Actions▼	=
Upper Bakken Shale	Geologic Top	11114		Actions▼	
Middle Bakken	Geologic Top	11132		Actions▼	
Three Forks Fm.	Geologic Top	11197		Actions▼	
Three Forks First Bench (B1)	Geologic Top	11217		Actions▼	
Pierre Fm.	Geologic Top	2137		Actions▼	
Greenhorn Fm.	Geologic Top	4830		Actions▼	




Mowry Fm.	Geologic Top	5230	Actions▼
Swift Fm.	Geologic Top	6140	Actions▼
Rierdon Fm.	Geologic Top	6612	Actions▼
Dunham Salt	Geologic Top	7157	Actions→
Pine Salt Member	Geologic Top	7441	Actions→
Minnekahta Fm	Geologic Top	7551	Actions▼
Opeche Fm.	Geologic Top	7585	Actions▼
Opeche A Salt	Geologic Top	7633	Actions▼

Amsden Fm.	Geologic Top	7911	Actions▼
Tyler Fm.	Geologic Top	8088	Actions▼
Kibbey Lime	Geologic Top	8665	Actions▼
Charles Fm.	Geologic Top	8810	Actions▼
Base Of Last Salt	Base of Last Salt	9563	Actions▼
Mission Canyon Fm.	Geologic Top	9781	Actions▼

^{**}Note: Zone Categories should basically indicate "Geologic Top" unless "Base of Last Salt". In the case of BLS, the bottom TVD must be indicated.


Step 7: Features & Cement

It would be advisable to have all information ready at your disposal before starting this section, because the feature may "time out" after a certain amount non-use time. Also, it is a good practice to click "Save" for Step 7 after each section is completed.




Step 7: Features & Cement Continued

Below is the minimum information needed to process the application for the "Surface Hole".




Step 7: Features & Cement Continued

Below is the minimum information needed to process the application for the <u>"Surface Hole"</u>. There is no need to indicate the Bottom Hole Footages From Nearest Section, because the NDIC Oil & Gas Division does not allow intentional deviation of the surface hole. However we will not return the application if it is populated.




Below is the minimum information needed to process the application for the "Vertical & Curve".

*Legal Entry Point into Pool & Spacing Unit: This info may be filled in by the operator, but is evaluated and corrected by Oil & Gas Division staff. It is an interpolated point between two survey stations. In this case, the well head is already at a legal point (with no back build)-so we need only be concerned with the Bakken Pool (strat limit: 50' above the top of the Bakken). (This point will be verified by TLH or NHE).



^{*(}pertaining to the directional plan above) Well head is legal with no back build, so we are compliant with the Spacing Unit setbacks. However, the legal entry point into the Bakken Pool is 50' above the Upper Bakken Shale: 11,114'TVD minus 50'=11,1064'TVD; which is between 111060.73TVD and 11101TVD. We will use aformentioned TVD's to get the coordinates for N/S & E/W.

Below is the minimum information needed to process the application for the "Vertical & Curve".



Step 7: Features & Cement Continued

Below is the minimum information needed to process the application for the "Vertical & Curve".

*The Bottom Hole Coordinates from Well Head indicate the End Of the Curve.


Based on the directional plan the EOC is:


Lower Bakken S	ilt								
11,369.50	74.07	186.00	11,197.00	-375.85	-39.50	376.13	11.00	11.00	0.00
Three Forks									
11,400.00 11,500.00 11,514.31	77.43 88.43 90.00	186.00 186.00 186.00	11,204.51 11,216.80 11,217.00	-405.24 -503.79 -518.02	-42.59 -52.95 -54.45	405.55 504.17 518.41	11.00 11.00 11.00	11.00 11.00 11.00	0.00 0.00 0.00
LP @ 90° Inc, Ho	ld - Three For	ks B1 Target -	- 7"						
11,554.31	90.00	186.00	11,217.00	-557.80	-58.63	558.22	0.00	0.00	0.00
Turn 2°/100'									
11,600.00	90.00	185.09	11,217.00	-603.27	-63.04	603.72	2.00	0.00	-2.00
11,700.00 11,800.00 11,854.10	90.00 90.00 90.00	183.09 181.09 180.00	11,217.00 11,217.00 11,217.00	-703.01 -802.94 -857.04	-70.17 -73.81 -74.32	703.51 803.47 857.57	2.00 2.00 2.00	0.00 0.00 0.00	-2.00 -2.00 -2.00



Step 7: Features & Cement Continued

Below is the minimum info needed to process the Lateral "wellbore type"







7. Features & Cement
8. Completion & Perforation
9. Proposed Work
10. Document Upload
11. Operator Assertions
12. Form Submit
13. Confirmation
14. Plan View
15. Stipulations
16. Review Checklist
17. Review Comments
18. Review

Туре	(API-12)	Status	Status	(MD	(MD ft	(TVD ft)	(in)	Actions
Vertical & Curve 1		Not Installe d	New	0	11514	11217	8.75	Actions▼
Lateral 1		Not Installe d	New	11514	21108	11217	6	Actions▼
Surface Hole 1		Not Installe d	New	0	2275	2275	13.5	Actions→

Wellbore Constru	ction Feature							
					▼ Advance	d Filtering	Actions ▼	\$
Feature ID ↑	Install Status	Record Status	Feature Top MD (ft)	Featur Bottom MD (ft)	ı (deci	Form	Actions	




<u>Wellbore Construction Feature: Casing.</u> While it is preferred that the casing is segmented into Weight and Grade/Type, it is not required at this time. We will not return the permit if the weights and grade/types are combined into one record. However, make sure all the wells on the pad are consistently reporting the same info.



* Indicates Required Field

Production Casing Wellbore Start*		•	Construction Not Installed Wellbore End	•	New	
Vertical & Curve 1		•	Vertical & Cur	ve 1		•
Feature Top MD (ft) *	Feature (ft) *	e Bottom MD	Outside Diame (decimal inche		Inside Diameto (decimal inche	
Weight (lbs)		Grade/Type		Burst	Pressure (psi)	
32		HCP-110	•	1122	0	
Feature Condition		Install Date		Remov	ve Date	
New	•		ä			
Pulled •	Conne	ction Type	•			
Description						
						.tl
					Can	cel Save

					* India	ates Requi	red Fie
Production Casing		•	Construction Not Installed	•	New	Status	
Wellbore Start* 1			Wellbore End				
Vertical & Curve 1		•	Vertical & Cur	rve 1			7
Feature Top MD (ft) *	Featu (ft) *	re Bottom MD	Outside Diame (decimal inche		Inside D (decimal	iameter Inches)	_
11400	115	14	7				
Weight (lbs)		Grade/Type		Burst F	Pressure (psi)	
29		HCP-110	•	1246	0		
Feature Condition		Install Date		Remov	e Date		
New	•		ä			Ê	
Pulled	Conn	ection Type					
•			•				
Description							
)
						Cancel	Sav



The above info is based off the operator's Casing Design Parameters as noted after this section.

B. Casing Design Parameters:

Surface Casing

<u>Interval</u>	Description	<u>Burst</u> (psi) ^a /SF	Collapse (psi)b/SF	Tension (klb)c/SF
0'-2275'	9%" 36PPF J-55 LTC	3520/2.29	2020/1.95	453/6.59

- a. based on frac gradient at shoe of 14 ppg
- b. based on full evacuation with 9 ppg fluid on backside
- c. based on casing string weight in 9 ppg mud String Weight in 9 ppg mud \approx 68690 lbs

Production Casing

<u>Interval</u>	Size	Burst (psi)a/SF	Collapse (psi) ^b /SF	Tension (klb)°/SF
2275'-8650'	7" 29# HCP-110 LTC	11220/1.6	8530/1.52	797/2.79
8650'-11400'	7" 32# HCP-110 LTC	11220/1.78	8530/1.09	897/11.76
11400'-11514'	7" 29# HCP-110 LTC	12460/1.6	12397/1.19	797/288.68

- a. based on 7000 psi frac pressure.
- b. based on full evacuation with 12.5 ppg pore pressure on backside
- c. based on casing string weight in 10.8 ppg mud String Weight in 10.8 ppg mud \approx 285739 lbs.

Production Liner

Tutomia1	Siza	D // 340E	Collapse	Tension
<u>Interval</u>	Size	<u>Burst</u> (psi) ^a /SF	(psi) ^b /SF	(klb)c/SF
10696'-21108'	4½" 11.6# HCP-110 LTC	10690/1.67	8830/1.21	279/3.12


- a. based on 7000 psi frac pressure.
- b. based on full evacuation with 0 ppg pore pressure on backside
- c. based on casing string weight in 8.33 ppg mud String Weight in 8.33 ppg mud \approx 102340 lbs.



*Make sure the "Verify Method" is BLANK. This is for NDIC Oil & Gas Division staff geologists.

Minimum info for permitting required is noted.


Associated Feature* Surface Casing 1 Record Status	Inside/Outside Casing? * Outside Top MD (ft)	Not Installed Bottom MD (ft)	•
Verify Method		menting Company	
Install Date	Re	move Date	
Description			
			.4)




		* Indicates	s Required F
Associated Feature *	Inside/Outside	Construction Status * 🚯	
Production Casing 1		Not Installed ▼	•
Record Status	Top MD (ft)	Bottom MD (ft)	
New	4230	11514	
Verify Method	C	Cementing Company	
	•	Schlumberger	
Install Date	F	Remove Date	
			=
Description			

Volume (sacks) are required. Ask that the operator fills out the Yield (cu ft per sack)

			* Indicates Required F
ssociated Ceme	ent Segment*	Cement Type *	Construction Status* 😉
C1	•	Class A Cement	▼ Not Installed ▼
ecord tatus	Compressive St	trength (psi) Weight (lbs	Slurry Consistency (Bu)
ead/Tail		Volume (Sacks)	Yield (cu ft per sack)
Lead	•	509	2.92
escription			
			Cancel





The above info is based off the operator's Proposed Cementing Program as noted below.

Surface Casing

Surface Casing						
CASING	SLURRY	FT. of	CEMENT TYPE	XC	WEIGHT	YIELD
CASING	CASINO SLOKKI	FILL	CEMENT TIPE	(%)	(ppg)	(ft^3/sx)
9-5/8"	Lead	1750	509 sxs of ALTCem S100-12 + 5% ACL-20 Accelerator + 2.00 lb/sk AXE-30 Extender + ACL-10 2.0 lb/sk Accelerator + 0.25 lb/sk ALC-10 (LCM). T.O.C. = SURFACE. Water Req = 17.8 gal/sx.	40%	11.5	2.92
9-5/8"	Tail	500	247 sxs of ALTCem S100-12 + 5% ACL-20 Accelerator + 2.00 lb/sk AXE-30 Extender + ACL- 10 2.0 lb/sk Accelerator + 0.25 lb/sk ALC-10 (LCM). T.O.C. = 1880. Water Req = 10.8 gal/sx.	40%	13	1.98

- A cement top job is required if cement fallback is greater than 10' below ground level.
- Top plugs shall be used to reduce contamination of cement by displacement fluid
- A bottom plug or other acceptable technique, such as a pre-flush fluid, inner string cement method shall be utilized to help isolate
 the cement from contamination by the mud fluid being displaced ahead of the cement slurry
- Formation at the shoe shall be tested to a minimum of the mud weight equivalent anticipated to control the formation pressure to the
 next casing depth or at total depth of the well. This test shall be performed before drilling more than 20 feet of new hole

Production Casing

CASPIG	CLIDDY	FT. of	CENTENTE TUDE	XC	WEIGHT	YIELD
CASING	CASING SLURRY		CEMENT TYPE	(%)	(ppg)	(ft³/sx)
7"	Lead	1882	148 sxs of ALTCem 165-X1 + 6.0 % AVS-50 Viscosifer + 0.25 lb/sk ALC-10 (LCM) + 0.70% AR-10 Retarder + 0.20 % AFL-10 Fluidloss. T.O.C. = 3939. Water Req = 6.4 gal/sx.	25%	12	2.54
7"	Tail	5402	653 sxs of ALTCem 100-X1 + 6.0 % AVS-50 Viscosifer + 0.25 lb/sk ALC-10 (LCM) + 0.70% AR-10 Retarder + 0.20 % AFL-10 Fluidloss + .20% ASR-20 Silica. T.O.C. = 6300. Water Req = 6.4 gal/sx.	25%	15.6	1.56

Cement volumes for the 7" Production Casing will be calculated to provide a top of cement of 4230'. Actual cement volumes may vary due to variations in the actual hole size and may be determined by caliper log, if available.

All waiting on cement (WOC) times will be adequate to achieve a minimum of 500 psi compressive strength at the casing shoe prior to drilling out.

Production Liner


CASING	CASING SLURRY	FT. of FILL	CEMENT TYPE	XC WEIGHT		YIELD
CASING			CEMENT TITE	(%)	(ppg)	(ft³/sx)
4-1/2" Liner	Tail	10,412	599 sxs of ALTCem P50-X1 + 4.0 % AVS-50 Viscosifer + 20.0 % Strength Retrogression + 0.5 % AFL-10 Fluidloss + 0.6% ADF-10 Defoamer+ 0.50% AR-20 Retarder + 0.30% AR-30 Retarder = .20% ASR-2-Silica. T.O.C. = 9817. Water Req = 9.4 gal/sx. See Cement Proposal.	15%	13.5	1.91

Form Navigation 8

Note:

-If top the top coordinates of the completion interval (7" casing point-AKA production casing) are the same as Longstring Casing Point section, then there is no need to add them again.

-Note whether or not the surface reservation boundary is intersected by Spacing/Drilling Unit.



Typical "Bakken" single laterals: 7" (production) casing point will be the "top" of the completion interval, and bottom will be dependent upon the type toe isolation.


Examples include:

Wet shoe with the ability to frac out the shoe: Bottom completion coordinates would be the TD of the well.


Wet shoe with no ability to frac out the shoe: Bottom completion coordinates would be the closest proposed survey point to the location the Bridge Plug in the toe.

Cemented Liner with no ability to frac out the shoe: Bottom completion coordinate would be the top of the cemented shoe.

No Liner: Bottom completion coordinate would be the TD of the well.




Note: Enter the following info if it is known at the time of permitting: Perforation Diameter, Perforation Spacing & Number of shots. The information displayed is the minimum we would allow. We would prefer that the operator indicate the top & bottom MD perforations. This information should be found on the Bakken Completion Schematic.



*This is extra space to explain the permit application. It may be used as a cover letter or otherwise it may remain blank.

It may also be used to indicate the deposition of the cuttings.

Form Navigation 10. Operator Assertions.



Separate the permitting documents into a minimum of 3 "Descriptive" groups & maximum of 6.

Example:

Type: APD Attachments, Decription: Plats (upload all).

Type: APD Attachments, Description: Directional plot & plan.


Type: APD Attachments, Description: Casing, Mud & Cementing Detail.

Type: APD Attachments, Description: Geologic Prognosis.

Type: APD Attachments, Decription: Affidavits & Gas Capture Plan (if required).

Type: APD Attachments, Description: Anti-collision plan (if required).


Form Navigation 11. Operator Assertions. Call the operator and discuss if there are only one or two that appear incorrect. Send the form back if there appear to be multiple issues.



PI: /A	File No.: N/A	Field: N/A	Type of Well: Oil & Gas		Type of New We	Work: II - Horizontal
ease ent	er information below.				* Indicates	Required Fi
Operator	Assertions *					
Assert	tions			Yes	No	N/A
Are the	well and production f	acility on the same	e pad?	•		
days and complet or if the one thou	nd not less that seven sted in the same pool, e operator is made aw	business days, to if publicly available are, if the complet	written notice, up to ten any operator of a well e information indicates ion intervals are within et or (402.34 meters) of			
	he operator acknowled tor to seek proper plug ck?					
leak-pr maintai remain	oof container (with pla ined on the well site be	icard) for filter soc eginning when the out, completion, ar	ine 1, 2014 a covered k disposal must be well is spud and must nd flow-back whenever			
Does th	he well pad block any	drainages?			•	
method	e operator confirmed v d of payment to be use sing of this application	ed for any fees as:		•		
	e operator provided no ed dwelling located wit		of any permanently ne proposed oil or gas			
	Has the operator reviewed any wells within 500' of the proposed wellbore and addressed anti-collision concerns?					
produc	rell is within 1000 feet of tion facilities located a g than the wellbore?		relling: Are the proposed ce from the occupied			
	oad between 2,640 fee	et and 10,000 feet	from the end of a public		•	

Is the well or production facility closer than 500' to an occupied dwelling?	0		0
Is the well pad located on an aquifer?			
Is the well pad located on/adjacent to unstable soils or areas with a high potential for soil instability (mapped or unmapped)?	0	•	0
Is the well pad located on/near surface coal, sand or gravel deposit?		•	
Is the well pad located within 33 feet of a section line?	0		0
Is the well pad located within a city's extra territorial boundary?			
ls the well pad located within a county, state or fed designated historic site, recreation area or wildlife management area?	0		0
Is the well pad within 2,640 feet from the end of a public use airport runway (If yes, there is a 45-day comment period required)?		•	
Is the well pad within 200 feet of the centerline of a state or federal highway on flat land or 400 feet in rough topography?	0	•	0
ls the well pad within a 100-year (or less) floodplain?		•	
Is the well pad within a well head protection area?	0		0
Is the well within a planned bypass route that has been proposed in an approved ten year, or less, county, state, or federal road master plan?			
ls this well or completion interval located within the external boundaries of the Fort Berthold Indian Reservation?	0	•	0
ls this well within 1,320 feet of a military facility?		•	
Is this well within an area of interest as it relates to public lands pursuant to NDIC PP 2.01 (If yes, a 10-day comment period required)?	0	•	0
Pursuant to the NDIC 43-02-03-31 (Well Log, Completion, and Workover Reports), the operator understands and will run porosity and resistivity logs on this well unless otherwise approved by the Director.	•		

#34478 MOEN 41-2-5TFH LOT1 2-154-99 365 FNL 525 FEL






Addendum

Discussion

The standard cemented shoe configuration involves a cemented liner, whereby redundant Toe Initiation Sleeves are run above the Float Collar, in addition to the standard float equipment. The wiper plug is designed to be pumped past the Toe Initiation Sleeve, exposing it to the wellbore for future use as a toe initiation point. In short, using the Toe Initiation Sleeves in conjunction with a standard cemented shoe configuration allows the operator to pump-down the first stage perforating guns on wireline, avoiding the more expensive option of perforating on tubing or with a tractor. This configuration ensures the fracture treatments do not exit the wellbore through the shoe, since the shoe joint(s) themselves will be full of cement, and the Toe Initiation Sleeves and Stage 1 perforations will be the deepest exit point for stimulation fluids.

50' offset from Section Line plus additional 40' discretionary offset



Case No. 27936 (Continued)
Order No. 30704

- (c) Proposed toe of the lateral including the location of the deepest perforation, completion sleeve, and/or external isolation packer.
- (12) The Completion Report (Form 6) for a horizontal well completed in the Banks-Bakken Pool shall include a well schematic which depicts the:
 - (a) Production casing setting depth at the heel relative to the spacing unit boundary;
 - (b) Completion style as open hole lateral, cemented liner or casing in the lateral, liner or casing externally isolated in the lateral by the use of packers, or other completion style; and
 - (c) Toe of the lateral including the location of the deepest perforation, completion sleeve, and/or external isolation packer.
- (13) The proper spacing for the development of Zone I in the Banks-Bakken Pool is hereby set at one horizontal well per 640-acre spacing unit.
- (14) Spacing units hereafter created in Zone I in the Banks-Bakken Pool shall consist of a governmental section.
- (15) Zone I in the Banks-Bakken Pool shall not be extended except by further order of the Commission after due notice and hearing.
- (16) The proper spacing for the development of Zone II in the Banks-Bakken Pool is hereby set at one horizontal well per standup 960-acre spacing unit.
- (17) Section 10 and the S/2 of Section 3; and Section 11 and the S/2 of Section 2, Township 152 North, Range 99 West, McKenzie County, North Dakota, are hereby designated standup 960-acre spacing units in Zone II in the Banks-Bakken Pool.
- (18) Spacing units hereafter created in Zone II in the Banks-Bakken Pool shall be standup spacing units designated by the Commission.
- (19) Zone II in the Banks-Bakken Pool shall not be extended except by further order of the Commission after due notice and hearing.
- (20) The proper spacing for the development of Zone III in the Banks-Bakken Pool is hereby set at one horizontal well per standup 1280-acre spacing unit.
- (21) Sections 6 and 7, Township 153 North, Range 97 West, McKenzie County, North Dakota, are hereby designated a standup 1280-acre spacing unit in Zone III in the Banks-Bakken Pool.
- (22) Spacing units hereafter created in Zone III in the Banks-Bakken Pool shall be standup spacing units consisting of two adjacent governmental sections.

Case No. 27936 (Continued) Order No. 30704

- (a) Measurement inaccuracies in the directional survey equipment need not be considered except when deemed necessary by the Director.
- (b) The lateral, heel portion of the lateral, or toe portion of the lateral in horizontal well bores shall be no closer than 500 feet to the most nearly parallel spacing unit boundary.
- (c) The Director is hereby authorized to reduce the setback from 500 feet to 200 feet for horizontal well bores where the angle of the heel portion of the lateral and the respective spacing unit boundary is less than 45° through the issuance of permit stipulations, whenever, in his opinion, the applicant has demonstrated that correlative rights will be protected.
- (d) The heel portion of the lateral in horizontal well bores where the angle of such is greater than 45° from the respective most nearly perpendicular spacing unit boundary, shall be no closer than 150 feet to said boundary.
- (e) The lateral or toe portion of the lateral in horizontal well bores where the angle of such is greater than 45° from the respective most nearly perpendicular spacing unit boundary, shall adhere to the following:
 - (i) For horizontal wells completed open hole, the total depth of the well bore shall be no closer than 150 feet to the boundary of the spacing unit;
 - (ii) For horizontal wells completed with the production liner or casing cemented in the lateral, the total depth of the well bore shall be no closer than 50 feet to the boundary of the spacing unit, unless the horizontal well is stimulated through the shoe at the toe of the lateral whereby the total depth of the well bore shall be no closer than 150 feet to the boundary of the spacing unit; and
 - (iii) For horizontal wells completed with the production liner or casing externally isolated in the lateral by the use of packers, the total depth of the well bore shall be no closer than 100 feet to the boundary of the spacing unit unless the horizontal well is stimulated through the shoe at the toe of the lateral whereby the total depth of the well bore shall be no closer than 150 feet to the boundary of the spacing unit.
- (11) The Application for Permit to Drill (Form 1) for a horizontal well to be completed in the Banks-Bakken Pool shall include a well schematic which depicts the:
 - (a) Proposed production casing setting depth at the heel relative to the spacing unit boundary;
 - (b) Proposed completion style as open hole lateral, cemented liner or casing in the lateral, liner or casing externally isolated in the lateral by the use of packers, or other completion style; and

"Typical" Whiting wet shoe digram 2/14/2020

Details of Standard Wet Shoe

Roggenbuck Federal 41-24-3TFX

Discussion

The "wet shoe" configuration involves a standard cemented liner, whereby the cement job is intentionally over-displaced by 5 barrels of displacement fluid, creating approximately 150' of uncemented annulus around the toe-portion of the liner. The wiper plug pumped to displace the cement contains a 'rupture disc' engineered to fail at a certain pressure, with the purpose of providing an economic method for toe initiation. In short, the wet shoe configuration allows the operator to pump-down the first stage perforating guns on wireline, avoiding the more expensive option of perforating on tubing or with a tractor. To ensure the fracture treatments do not exit the wellbore through the wet-shoe, a frac-plug will be set below the lowermost perforation and above the rupture disc, effectively sealing the wet shoe and forcing the fracture treatment out the perforations. fluids.

200' offset from Section Line plus additional 40' discretionary offset

